

Product Kenmerken:

- Hoge precisie: het meetbereik van 0-33.000V over de traditionele 0-20.000V header.
- Flexibele supply: Er is geen noodzaak om isoleren voeding, kunt u het systeem gemeenschappelijke grond. (opmerking: Als u 0.1 mV resolutie gebruik geïsoleerde voeding. Anders de nauwkeurigheid drop een orde van grootte
- **Variabele precisie:** Precisie automatische verandering onder 4.3 V, de hoogste resolutie van 0.1 mV, precisie automatische 4.3 V bovenstaande wijzigingen, de hoogste resolutie van 1 mV Connection is eenvoudig, gewoon moeten halen twee lijnen, een gezamenlijke reverse bescherming, dan branden niet

Technische Parameters:

- **Gewicht:** 16g
- **Display kleur:** Rood/geel/blauw/groen
- **Weergavemodus:** Vijf 0.36 LED digitale buis
- **Update rate:** > 3s/tijd
- **Fysieke grootte:** 48x29x22mm (L * W * H)
- **Opening grootte:** 45x26mm (L * W)
- **Voedingsspanning:** 3.5-30V
- **Lead draad lengte:** 14 cm
- **Meetbereik:** DC 0-4.3000-33.000V
- **Operatie temperatuur:** -10 graden ~ 65 graden
- **Meting nauwkeurigheid:** (0.03% + 2 woorden) {betekent de tafel ergste geval maximale fout van minder dan 10mv normaal binnen fout 2mv}

Rode lijn 1: Voeding + **Zwarte lijn 1:** Voeding-

Rode lijn 2: VIN + **Zwarte lijn 2:** VIN-

OPMERKING: Header nodig onafhankelijke voeding. Voeding bereik is 3.5-30 V dc. Wanneer zwarte draad en rode draad zijn ingeschakeld om met de voeding, header zal display 0.0000 (wanneer de meetlijn is bungelende, de header zal een of twee base) . Rode VIN + en zwarte lijn VIN- zal worden overgeschakeld naar de meting circuit. De gemeten spanning bereik is 0-33.000 V dc.

DC-DC: 0-4.3000V De hoogste resolutie van 0.1 mV

Product Features:

- High precision : the measurement range of 0-33.000V over the traditional 0-20.000V header.
- Flexible supply: There is no need to isolate power supply, you can use the system common ground.(Note: If you need 0.1 mV resolution please use isolated power supply. Otherwise the accuracy drop an order of magnitude
- **Variable precision:** Precision automatic change below 4.3 V, the highest resolution of 0.1 mV, Precision automatic 4.3 V above changes, the highest resolution of 1 mV Connection is simple, just need to pick up two lines, a joint reverse protection, then do not burn

Technical Parameters:

- **Weight:** 16g
- **Display color:** Red/yellow/blue/green
- **Display mode:** Five 0.36 LED digital tube
- **update rate:** > 3s/time
- **Physical size:** 48 x 29 x 22 mm (L*W* H)
- **Opening size:** 45 x 26 mm (L*W)
- **Supply voltage:** 3.5-30V
- **Lead wire length:** 14 cm
- **Measurement range:** DC 0-4.3000-33.000V
- **Operation temperature:** -10 degrees~65 degrees
- **Measurement accuracy:** (0.03%+ 2words) {means the table worst case maximum error of less than 10mv normal within error 2mv}

Red line 1 : Power Supply + Black line 1: Power Supply -
Red line 2 : VIN + Black line 2: VIN -


NOTE: Header need independent power supply. Power supply range is 3.5-30 V dc. when black wire and red wire are switched to with the power supply ,header will display 0.0000 (when the measuring line is dangling ,the header will display one or two base) . Red VIN + and black line VIN - will be switched to the measurement circuit. the measured voltage range is 0-33.000 V dc.
DC-DC: 0-4.3000V the highest resolution of 0.1 mV






DC-DC: 0-33.000V De hoogste resolutie van 1 mV



Producten display







Four Lines: 14cm